



THE TOWNSHIP OF BONNECHERE VALLEY

TENDER No. BV-24-01

REHABILITATION OF ZADOW ROAD

ADDENDUM NO. 04

(3 PAGES)

March 20, 2024

This Addendum is issued to correct, change or clarify the Contract documents and it shall become part of all the Contract documents. Contractors shall include all costs associated with this Addendum in their bid price. Contractors shall include this Addendum in their tender submission.

INSTRUCTIONS TO BIDDERS

1. Remove and replace *Section A – Schedule of Items and Prices* with the attached *Section A – Schedule of Items and Prices*. The attached *Section A – Schedule of Items and Prices* supersedes *Section A – Schedule of Items and Prices* in Addendum No. 3. Contractor is to complete and submit the schedule on the following pages in place of the SCHEDULE OF ITEMS AND PRICES with the complete tender package.

SECTION A – SCHEDULE OF ITEMS AND PRICES

Contractor is to complete and submit the schedule on the following pages in place of the SCHEDULE OF ITEMS AND PRICES with the complete tender package. Please note that the duplicate Item, Item B-6 – Monitoring Well Abandonment has been removed. There are no other changes to items.

SCHEDULE OF ITEMS AND PRICES

ITEM NO.	SPEC. CODE	ITEM DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE	AMOUNT
SECTION A – GENERAL						
A-1	OPSS 706, SP1	Traffic Control	LS	1		
A-2	OPSS 805, SP2	Sediment and Erosion Control	LS	1		
A-3	SP19	Monitoring Well Abandonment	ea	2		
SECTION B – REMOVALS						
B-1	OPSS 180, OPSS 206, SP3, SP4	Earth Excavation (Grading)	m ³	2,400		
B-2	OPSS 180, OPSS 802, SP3, SP5	Earth Ditch Cleanout	m	4,000		
B-3	OPSS 510, SP6	Removal and disposal of all pipes and culverts (any size and type)	m	100		
B-4	OPSS 510, SP16	Removal, salvage and reinstate signs	ea	9		
B-5	OPSS 510, SP13	Removal, salvage and reinstate mailbox	ea	2		
SECTION C – DRAINAGE						
C-1	OPSS 421, SP7	400mm Galvanized CSP Culvert	m	18		
C-2	OPSS 421, SP7	600mm HDPE Culverts	m	91		
SECTION D – ROADWAY						
D-1	OPSS 301, OPSS 330, OPSS 510, SP3, SP8	In-Place Processing and Restoring Roadway Surfaces (200mm Depth)	m ²	15,700		
D-2	OPSS 314, OPSS 501, SP8, SP10,	Granular 'A' - Roadway – 5,222 tonnes - Driveways – 78 tonnes	t	5,300		
D-3	OPSS 314, OPSS 501, SP10	Granular 'B TYPE II	t	7,000		
D-4	OPSS 1860, SP11	Biaxial Geogrid Composite	m2	5,300		
D-5	OPSS 310, OPSS 311,	50mm Surface Course Asphalt - HL4 PGAC 58-34	t	2,050		

ITEM NO.	SPEC. CODE	ITEM DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE	AMOUNT
	SP9, SP18	- Roadway – 2,044 tonnes - Driveways – 6 tonnes				
SECTION E – REINSTATEMENT						
E-1	OPSS 710, SP14	Solid Yellow - 100 mm wide - Pavement Markings	m	2,300		
E-2	OPSS 710, SP14	Solid White - 600 mm wide - Pavement Markings	m	8		
E-3	OPSS 802, SP15	Topsoil from Stockpiles	m ³	920		
E-4	OPSS 804, SP15	Seed and Mulch	m ²	9,200		
SUB-TOTAL						
HST (13%)						
TOTAL TENDER PRICE						

NOTE: It is understood that the estimated quantities in the foregoing are solely for the purpose of facilitating the comparison of bids and the Contractor's compensation will be computed upon the basis of the actual quantities in the completed work, whether they be more or less than shown herein.

REPORT TENDER TOTAL IN WRITING

CONTRACTOR'S FEDERAL GOODS AND SERVICES TAX REGISTRATION TAX REGISTRATION NUMBER

For further information please contact:

Alex Siciliano, P.Eng.
Egis Canada Ltd.
alex.siciliano@egis-group.com

- END OF ADDENDUM NO. 04 -